

Developing an Integrated Design Support Framework to Enable Mass-Customisation in Multi-Storey Timber Building Projects

by Alireza Jalali Yazdi

Thesis submitted in fulfilment of the requirements for
the degree of

Doctor of Philosophy

under the supervision of
Dr. Alireza Ahmadian Fard Fini
Dr. Ali Akbar Nezhad
Dr. Michael Er

University of Technology Sydney
Faculty of Design, Architecture and Building

August 2022

CERTIFICATE OF ORIGINAL AUTHORSHIP

I, Alireza Jalali Yazdi declare that this thesis is submitted in fulfilment of the requirements for the award of Doctor of Philosophy, in the School of Built Environment, Faculty of Design, Architecture and Building at the University of Technology Sydney.

This thesis is wholly my own work unless otherwise referenced or acknowledged. In addition, I certify that all information sources and literature used are indicated in the thesis.

This document has not been submitted for qualifications at any other academic institution.

This research is supported by the Australian Government Research Training Program.

Signature:

Production Note:
Signature removed prior to publication.

Date: 23/08/2022

Acknowledgement

To my parents, for all their support and unconditional love

This is a thesis by compilation

Declaration of Publications

The following publications, which have arisen from the research for this thesis, are listed below:

1. **Alireza Jalali Yazdi**, Alireza Ahmadian Fard Fini, and Perry Forsythe.
"An Integrated Product Planning and Design Platform in the Context of Housebuilding Industry." Construction Research Congress 2020: Computer Applications. Reston, VA: American Society of Civil Engineers, 2020.
2. **Alireza Jalali Yazdi**, Alireza Ahmadian Fard Fini, and Perry Forsythe.
"Mass-customisation of cross-laminated timber wall systems at early design stages." Automation in Construction 132 (2021): 103938.
3. **Alireza Jalali Yazdi**, Alireza Ahmadian Fard Fini, Ali AkbarNezhad, Michael Er.
"DfMA-oriented Optimization of Cross-Laminated Timber wall systems in multi-storey buildings"
4. **Alireza Jalali Yazdi**, Alireza Ahmadian Fard Fini, Ali AkbarNezhad, Michael Er.
"Crane Scheduling for Efficient Installation of Prefabricated Modules in Multistorey CLT Buildings"

Publication status:

- Item 1: Accepted and published.
- Item 2: Accepted and published.
- Item 3: Under revision for re-submission.
- Item 4: Under revision for re-submission.

Note: Items 1 to 4 correspond to chapters 3 to 6 in this thesis in the same order.

The extent of the contribution of the student and other authors:

The major part of the research, including the literature review, developed methodology, and verification of the results, has been done by the student in all papers. Other authors provided guidance and insights to improve the articles and, in some cases, revised the writing of the articles.

Signature of Author

Alireza Jalali Yazdi

Production Note:
Signature removed
prior to publication.

Date:

28/03/2023

Signature of Co-Author

Perry FORSYTHE

Production Note:
Signature removed
prior to publication.

Date:

6/4/2023

Signature of Co-Author

Michael Er

Production Note:
Signature removed
prior to publication.

Date:

6/4/2023

Signature of Co-Author

Ali Akbar Nezhad

Production Note:
Signature removed
prior to publication.

Date:

6/4/2023

Signature of Co-Author

Alireza Ahmadian Fard Fini

Production Note:
Signature removed
prior to publication.

Date: 21/4/2023

Abstract

The building industry has adopted mass-customisation (MC) strategies to address efficiency issues associated with the customised nature of this sector. Multi-storey apartment buildings constitute a large segment of the Australian building sector, which possesses significant potential for MC. MC aims to provide choices for heterogeneous apartment demands in a prefabricated construction context. It intends to deliver marketable building products at a competitive cost close to mass-produced buildings. To maximise their benefits, mass-customisation strategies must be implemented from early design stages by developing a custom product that can be efficiently manufactured, transported and assembled onsite. Implementation of general design rules, such as guidelines provided by Design for Manufacture and Assemble (DfMA), at the early design stages can enable the mass-customisability of the final building product. Implementing such generic DfMA rules is challenging, particularly due to the mathematical complexity of the building design problem. To successfully address this challenge, a systematic and automatic approach is necessary for exploring different design alternatives. However, the literature is slim in proposing a practical solution to optimise the design for MC. Such an optimisation platform must incorporate offsite manufacturing processes and efficient onsite assembly and installation operations into the design process.

This research introduces a design support framework that enables MC of multi-storey buildings by incorporating both offsite manufacturing and onsite assembly requirements. The framework consists of three main components: (1) a design optimisation model to maximise standardisation while maintaining architectural flexibility, (2) a framework for transferring the optimisation results to a digital design platform, and (3) an onsite installation optimisation model for crane scheduling to avoid the formation of bottlenecks in assembling mass-customised components. Due to their increasing market uptake, and their high potential for customisation, Cross-Laminated Timber (CLT) buildings are chosen as the case studies for the implementation of MC strategies. The mass-customised building designs were automatically generated and thoroughly explored using evolutionary algorithms. The optimal design solutions were visualised on a Building Information Modelling platform and then were used to generate an accurate bill of quantities for factory production. Results of the case studies showed that up to a 20% decrease in the CLT waste and a 10% decrease in the installation, delays are achievable by adopting the proposed methodologies. The outcomes of this research can be used by the building industry to achieve mass-customised designs that result in minimal waste during manufacture and a more productive onsite installation.

Contents

Declaration of Publications	iv
1 Introduction	1
1.1 Productivity issues and mass-customisation	2
1.2 Research gap	7
1.3 Research questions	8
1.3.1 Question 1	9
1.3.2 Question 2	10
1.4 Research objectives	10
1.5 Research scope	11
1.5.1 The market	12
1.5.2 The construction system	14
1.5.3 The design focus	15
1.5.4 Manufacturing scope	16
1.5.5 Onsite assembly scope	17
1.6 Thesis organisation	17
1.6.1 Chapter 1: Introduction	18
1.6.2 Chapter 2: Theories and concepts	18

1.6.3	Chapter 3: A conceptual framework for applying Mass-Customisation (MC) in building design	19
1.6.4	Chapter 4: Developing a design support tool for mass-cusomising the CLT buildings	19
1.6.5	Chapter 5: A practical framework for automated design of CLT buildings for mass-customisability in a digital environment	20
1.6.6	Chapter 6: An algorithm for efficient onsite installation of mass-customised systems	21
1.6.7	Chapter 7: Conclusions	21
2	Theories and Concepts	22
2.1	Theoretical framework	23
2.1.1	The economic perspective	24
2.1.2	Operations management perspective	29
2.2	MC as a response to the productivity issue	35
2.2.1	MC definitions	36
2.2.2	An overview of state of the art	37
2.3	Supply chain implications of mass-customisation strategies	42
2.3.1	Production strategies	43
2.3.2	CODP in the construction industry	48
3	A Conceptual Framework for Applying Mass-Customisation in Building Design	53
3.1	Overview	54
3.2	Introduction	55
3.3	Literature review	58
3.4	Product architecture	62

3.5	Automated product planning platform	65
3.6	Automated project design platform	65
3.7	Conclusions and discussion	67
4	Developing a Design Support Tool for Mass-Customising the CLT	
	Buildings	68
4.1	Overview	69
4.2	Introduction	70
4.3	Literature review	73
4.4	CLT buildings	76
4.4.1	Preliminary design of the member cross-sections	80
4.4.2	Section design	84
4.5	The Cutting Stock and Bin Packing problems	84
4.5.1	The cutting stock problem	85
4.5.2	The Bin Packing Problem	86
4.5.3	The structural wall design problem	87
4.6	Mathematical representation of the model	89
4.7	Solution search method	92
4.7.1	Generating the initial population	95
4.7.2	Solution evaluation	99
4.7.3	Genetic operators	100
4.7.4	New generation selection	103
4.8	Case study	103
4.9	Results and discussion	105
4.10	Conclusions	108
5	A Practical Framework for Automated Design of CLT Buildings for	
	Mass-Customisability in a Digital Environment	111

5.1	Overview	112
5.2	Introduction	112
5.3	Literature review	115
5.3.1	Design for Manufacture and Assembly	116
5.3.2	Architectural and Structural Optimisation	117
5.3.3	Production Optimisation	119
5.3.4	Summary	120
5.4	Methodology	121
5.4.1	Design for Manufacture and Assembly (DfMA)-Oriented Design of the Cross-Laminated Timber (CLT) Structural Wall System	121
5.5	DfMA-enabled modelling and optimisation of the CLT wall systems	128
5.5.1	Optimisation constraints	132
5.5.2	The bin packing process and the objective function	134
5.5.3	Initialisation of the walls class instances	135
5.5.4	Building Modelling and Visualisation	136
5.6	Case project	139
5.7	Conclusions	147
6	An Algorithm for Efficient Onsite Installation of Mass-Customised CLT Systems	149
6.1	Overview	150
6.2	Introduction	150
6.3	Literature review	153
6.3.1	Crane path planning	154
6.3.2	Lifting sequence optimisation	155
6.4	Methodology	157
6.4.1	Lifting time estimation	157

6.5	Problem definition	163
6.6	Problem modelling	165
6.7	Results and discussion	168
6.8	Solution generation workflow	168
6.9	Case study	172
6.10	Discussion	177
6.11	Conclusions	179
7	Conclusions	181
7.1	Conceptual framework for integrating design and the supply chain	185
7.1.1	Methodology	185
7.1.2	Chapter's efforts to fill the research gap	185
7.1.3	Chapter contributions to research and practice	186
7.1.4	Chapter's response to the Research Questions	187
7.1.5	Methodological limitations and recommendations	187
7.2	Design support tool for mass-customising CLT structures	188
7.2.1	Methodology	189
7.2.2	Chapter's efforts to fill the research gap	189
7.2.3	Chapter contributions to research and practice	190
7.2.4	Chapter's response to the Research Questions	192
7.2.5	Methodological limitations and recommendations	192
7.3	Automated design framework for mass-customising CLT buildings .	193
7.3.1	Methodology	194
7.3.2	Chapter's efforts to fill the research gap	194
7.3.3	Chapter contributions to research and practice	195
7.3.4	Chapter's response to the Research Questions	196
7.3.5	Methodological limitations and recommendations	197

7.4 Ensuring optimal onsite installation of mass-customised CLT systems	198
7.4.1 Methodology	199
7.4.2 Chapter's efforts to filling the research gap	199
7.4.3 Chapter contributions to research and practice	200
7.4.4 Chapter's response to the Research Questions	201
7.4.5 Methodological limitations and recommendations	203
List of Acronyms	204
Bibliography	207

List of Figures

1.1	A summary of the research scope	11
1.2	Value of building approved, by building type	12
1.3	Building classifications under the National Construction Code (NCC)	13
1.4	Thesis organisation and its connection to research objectives	18
2.1	A summary of theories and concepts leading to the formulation used in chapter 4	34
2.2	Production strategies based on the CODP	44
2.3	An example of comparing production strategies based on the CODP and standardisation of components in a product	47
2.4	Customisation strategies based on the CODP	50
3.1	Platform-based hierarchical decomposition of a building product .	64
3.2	Overview of the product planning and design platform	66
4.1	CLT panel (a), CLT assembly from the inside (b), and outside (c) . .	77
4.2	Example of Computer-Numeric Control (CNC) machines	78
4.3	Illustration of CLT panelised structural system	80
4.4	Indicative span for CLT floor panels	83

4.5	Different types of CLT billets: (a) Longitudinal panel, typically used for floor and beams, and (b) Transverse panel, typically used for wall panels	85
4.6	Illustrative example of a structural floor plan in 2D (top left) and 3D (bottom left), and billet cuts based on the wall lengths	88
4.7	Optimisation process employed by the GA	95
4.8	General representation of each solution	96
4.9	Illustration of the example permutation	98
4.10	Example of the permutation crossovers	101
4.11	Mutation operators: (a) Swapping, (b) Reversion, and (c) Insertion .	102
4.12	Illustration of the hypothetical case example	104
4.13	Example case's solution	108
5.1	CLT billets used for (a) Structural walls (stronger in the shorter dimension), and (b) Floors (stronger in the longer dimension) . . .	122
5.2	Example floor plan with a one-way spanning floor system	125
5.3	Example scenario of CLT wall optimisation problem; the determined section lengths (L1-L3) and the resulting wall lengths (left), and the optimum cutting plan (optimisation variable) on different billet types imposing minimum amount of wastes (W_{mn}) .	130
5.4	Overview of the optimisation process utilised by the framework . .	131
5.5	Problem inputs structure	132
5.6	Excel spreadsheet output of the Python optimisation results	137
5.7	Dynamo visual program and script developed to convert optimisation results into Revit model	139
5.8	Visual output of the Dynamo script in Revit project environment . .	144
5.9	Illustrative example of generated bill of quantities	146
6.1	Loaded lifting in horizontal (left); and vertical planes (right)	162

6.2	Different Classes and methods utilised for modelling the problem .	166
6.3	Visual demonstration of classes and methods: (A) site layout, (B) details of the stacks, and (C) Example of stacking for transportation	167
6.4	The process of random solution generation	171
6.5	Details of the initial problem conditions, including (a) the demand locations and types on the footprint, crane location, staging areas, and stacks of panels, and (b) Details of stacks	173
6.6	Illustration of different scenarios of panel installation priorities . .	175

List of Tables

2.1	A summary of the economic principles	28
2.2	A summary of operations management principles	32
2.3	Objectives of transition towards MC in different production contexts	47
3.1	Modularization aspects, their tools and objectives in the literature .	60
3.2	Modularization aspects, their tools and objectives in the literature .	62
4.1	Length constraint and demands of each floor plan section	104
4.2	Material Costs	104
4.3	GA parameters	105
4.4	Results of the optimisation run instances	105
4.5	Optimisation results; section lengths and billets	106
4.6	Cutting plan of the example problem	106
5.1	The current framework's scope	127
5.2	Notations	133
5.3	Wall panel sizes for different wall types	140
5.4	Acceptable length ranges for each wall section in Fig. 5.2	140
5.5	Price of different panel sizes	141
5.6	Optimum section lengths	141
5.7	Detailed panel cut plan for enforced standardisation	142
5.8	Detailed panel cut plan for free optimisation	142

6.1	Specifications of the panels, corresponding to their assembly demands in the case example	175
6.2	Specifications of the luffing tower crane	175
6.3	A summary of the optimisation results for different scenarios (double-handled panels are highlighted in black)	177